

# Installation Guide Spel Vertical Tank

# **Fibreglass Wetwell**



spel.co.nz

# TABLE OF CONTENTS

A. Handling and Preparation
B. Site Preparation
C.Anti Floatation Ballast FRP Wetwell 3
D. Bed and Backfill
E.Wetwell Installation with a Fibreglass Underground Tank 4
F. Piping Penetrations / Fittings 5
G. Invert
H.Top Pad
J. Wet Hole Installation 7
Table 1

#### INTRODUCTION

These instructions, while using the word "wetwell", will pertain to all wetwells, lift stations, vertical pump vaults and basins.

#### SAFETY

These instructions should not be interpreted in any way to put one's health at risk, or to harm property and/or the environment. The following definitions will serve as a guide when reading this manual:

# **A**WARNING

Indicates a potentially hazardous situation, which if not avoided could result in death or serious injury.

# **A** CAUTION

Indicates a potentially hazardous situation, which if not avoided may result in minor or moderate injury.

# CAUTION

A caution without the safety alert symbol indicates a potentially hazardous situation, which if not avoided may result in property damage.

#### **IMPORTANT INFORMATION**

Proper installation of each wetwell is essential:To ensure the safety of all the individuals involved in the installation.

• To prevent wetwell damage and/or failure, which could lead to product loss and environmental contamination.

• To validate the wetwell warranty.

#### **GENERAL INFORMATION**

# **A**WARNING

Wetwells are a confined space per OHS guidelines. Follow proper confined space safety procedures.

SPEL fibreglass wetwells are designed for installation with concrete top pad and bottom slabs. The following instructions reflect the approved methods for installing wetwells. Follow all OHS, Federal, State or Local, safety and environmental codes and regulations

## WETWELL WARRANTY ACTIVATION

• These instructions must be followed.

• The Wetwell Installation Checklist must be properly completed and signed by the owner's representative and the installing contractor. • The Wetwell Installation Checklist, these instructions, and any correspondence related to the wetwell installation must be retained by the

owner and provided to GA to validate any future warranty claim. The warranty in effect at the time of delivery will apply and is available from SPEL Environmental.



#### **BEFORE YOU BEGIN**

- Read, understand and follow these instructions.
- Barricade the work area.

• Review and prepare to complete the installation checklist as the installation progresses.

If you have questions on other wetwell installation details, call Technical Support at +61 2 8705 0255

# A. HANDLING AND PREPARATION

## **A**WARNING

Do not stand on or under wetwell while it is being lifted. This could result in personal injury or death.

• Do not drop or impact the wetwell.

• Wetwells should be stored horizontally and chocked, using only appropriate materials such as sandbags, tires, or other soft or pliable materials.

• Upon wetwell delivery and when lifting wetwell, visually inspect entire exterior surface of the wetwell for shipping or handling damage.

• If the wetwell must be moved by rolling, ensure that ground to be traversed is smooth and free of rocks, debris, or other hard objects.

• Do not roll or set the wetwell on any pipe stubout, accessory or appurtenance installed on the wetwell.

• The contractor is responsible for rigging, unloading and securing the wetwell.

• When lifting the wetwell in the horizontal position, use two slings with a spreader bar.

• Use a minimum of two lift lugs when pivoting the wetwell from horizontal to vertical.

• Utilize all lift lugs provided at the wetwell top for vertical lifting.

• Only a pliable strap or rope should contact the wetwell, do not use chains, steel cables or hard metallic slings.

# **B. SITE PREPARATION**

Dimensions of the excavation should be wide enough to provide sufficient working room around the wetwell.

Minimum anti floatation ring and ballast dimensions are specified in (Table I, page 7)

Anti floatation ring and ballast designs in (Table 1, page 7) meet Australian Standard Code S3600A.

(Dead load resisting floatation have a factor of safety of 0.9 applied.)

#### C. ANTI FLOTATION BALLAST FRP WETWELLS

# A WARNING

Collapsing excavation walls can cause injury or death. Do not enter the wetwell excavation unless necessary and in compliance with OHS regulations. Follow OHS guidelines for excavations.

#### WETWELLS

• Lower Wetwell onto Compacted Base then place Wet concrete around the Unit covers 2 x Ribs plus meets the Ballast Quantity in (Table I and figure I, page 7.)

Cold concrete joints are not allowed. Fibreglass solid bottom wetwells with external reinforcing ribs must be installed in a continuous and monolithic concrete pour. Concrete must extend 75mm above the second rib from the wetwell bottom, and around the entire circumference of the wetwell. (Refer to figure 1, page 7)

• Concrete slab must fill all gaps and voids in and around the external tank reinforcing ribs.

• It may be necessary to add ballast (water) inside the wetwell to counteract buoyancy until the concrete is cured.

# ANTI FLOATATION RING CONCRETE SLAB

Use minimum 20 mpa concrete for anti floatation and ballast Final concrete depth, size, thickness and reinforcements shall meet the minimum requirements in these instructions and applicable tables. Anti floatation ring should extend a minimum of (refer to table 1, page 7) in all directions from the wetwell outer diameter.

# **A** CAUTION

Voids in the concrete slab around external structural anchors will result in product damage and environmental contamination.

### **D. BED AND BACKFILL**

Proper backfill selection and compaction is required for a proper installation. The allowed backfills are shown in Table D-I along with the degree of compaction required.

#### Table D-I

Bed and Backfill Compaction				
Soil type-pipe bedding material (Unified Soil Classification System See Table D-2)	Minimum Degree of Compaction Required*			
Fine - grained soils (Liquid Limit < 50) with medium to no plasticity with less than 25% coarse grained particles. <b>CL, ML, ML - CL,</b>	High			
Fine grained soils (Liquid Limit < 50) with medium to no plasticity with more than 25% coarse grained particles. <b>CL, ML, ML - CL</b>	Moderate			
Coarse grained soils containing more than 12% fines. <b>GM, GC, SM, SC</b>	Moderate			
Coarse grained soils with less than 12% fines, <b>GW, GP, SW, SP</b>	Slight			
Coarse grained soils with less than 12% fines. <b>GW, GP, SW, SP</b>	Dumped			

\* Degree of compaction:

• Dumped - No compaction effort.

• Slight - Some compactive effort. In-place density <85%

standard compaction. Or < 40% modified compaction.

• Moderate - Intermediate level of compactive effort, In-place density >/=85% and < 95% standard compaction, or >/=40% and <70% modified compaction.

 High - Considerable compactive effort. In-place density >/= 95% standard compaction, or >/= 70% modified compaction

 The difference in the "dumped" and "slight" degree of compaction tion values are significant and are based on the method of construction, not the measured densities.

"Dumped" means that there is absolutely no compaction of the embedment soil. "Slight" means there was something done that increased the soil density, even if minor, such as water settling, jetting, flooding, equipment travel, and in some cases, foot traffic. • For stable soils (cohesion  $\geq$  36 kpa and / or a bearing capacity  $\geq$  170 kpa a minimum 300mm of backfill must be placed around the wetwell.

• For unstable soils (cohesion  $\leq$  36kpa and ultimate bearing capacity  $\leq$  170 kpa).

- Wetwells 1200mm diameter or smaller require a minimum 600mm of backfill around the entire circumference of the wetwell.

- Wetwells larger than 1200mm diameter require a minimum backfill of  $^{1\!/_{2}}$  the wetwell diameter around the entire circumference of the wetwell.

• If muck, bog or peat are present, consult with a Geotechnical Engineer for backfill and excavation requirements.

• For permafrost conditions, consult with a Geotechnical Engineer for backfill and excavation requirements. Keep backfill dry and free of ice in freezing conditions. Ensure that no foreign objects such as large stones, concrete clumps, tree roots/limbs, or debris is in the backfill surrounding the wetwell.

Prevent large surges of backfill from displacing the wetwell.

#### Table D-2

Letter and Definition	Second Letter and Definition
G Gravel	P Poorly Graded
S Sand	(uniform particle sizes)
M	W Well Graded
C Clav	(diversified particle sizes)
	H High Plasticity
OOrganic	LLow Plasticity

# E. WETWELL INSTALLATION WITH A FIBREGLASS UNDERGROUND TANK

# **A** CAUTION

Not using approved backfill material may result in tank failure and environmental contamination.

If the wetwell is installed in the same excavation as an underground fibreglass tank, the backfill around the wetwell must also meet the tank backfill requirements so as to not compromise the tank installation. Tank backfill requirements are more restricted and strict conformance to the tank backfill requirements in MAN 600 must be met for both the wetwell and tank.

# F. PIPING PENETRATIONS / FITTINGS

# ACAUTION

Always wear safety glasses and protective clothing when cutting on the wetwell, failure to do so can result in personal injury.

• Pipe penetration cutouts should be round holes and should be no larger than the pipe diameter plus 25mm.

- Make cuts using a saw with a masonry or diamond grit blade.
- Do not use an axe or other impact type tools.

• Accessories must be installed and used in strict accordance with the manufacturer's instructions.

• All piping must have a flexible connector installed directly on the fitting or accessory to allow for a minimum 15mm differential settlement between the wetwell and the pipe. If more than 15mm differential settlement is expected, choose a flexible connector designed for the expected settlement. Do not backfill around the wetwell until the concrete slab has hardened.

Add backfill in maximum 900mm lifts evenly around the wetwell to avoid uneven backfill loads.

• A flexible joint on each connecting pipe is required to relieve stresses from differential backfill movement or soil consolidation. Backfill should be added to the invert elevation of each connecting pipe, the connection made and sealed, before continuing to backfill.

# **A**WARNING

To prevent fire or explosion hazard, GA recommends air driven tools whenever possible. DO NOT use power tools where flammable vapors or liquids exist. Also, when electric hand tools are used, be aware of potential shock hazards. Wear protective clothing and eye protection.

Wetwells may be a confined space. Follow proper safety procedures.







EXPLOSION

#### G. INVERT

Invert specified by Certified Engineer. The invert may be at any angle and may project up the wetwell any distance.

# H. TOP PAD

The wetwell is designed to support the dead weight of an 200mm thick square pad 600mm larger than the diameter of the wetwell (centered on the wetwell) along with a dynamic T-44 traffic load as long as the pad is designed to distribute the loads on the wetwell perimeter and not on the interior of the lid.

If the static load will exceed the 200mm pad weight or the traffic load will exceed T-44, the pad must be 1200mm larger than the wetwell diameter (centred on the wetwell) and all of the pad and / or traffic loads must be supported by the soil around the wetwell and not by the wetwell itself.

Fibreglass flat tops 1000mm through 2500mm diameter are designed to support 200mm concrete pads without internal supports while the concrete cures.

The concrete pad must be designed to be self supporting after cured.

The pad shall be specified by the Certified Engineer.

#### FIBREGLASS FLAT TOPS WITHOUT TRAFFIC LOAD (See Figure H-1, Page 6)

• The pad must be larger than the wetwell a minimum of 300mm in all directions.

• Maximum 200mm concrete pad thickness.

#### FIBREGLASS FLAT TOPS WITH TRAFFIC LOAD (See Figure H-2, Page 6)

• The pad must be larger than the wetwell a minimum of 600mm in all directions.

• The Certified Engineer shall specify the pad strength and reinforcement so that the static weight of an 200mm thick square pad (no more than 600mm larger than the diameter of the wetwell centred on the wetwell) along with a dynamic T-44 traffic load must be distributed on the wetwell perimeter and not on the interior of the lid.

• If either the static pad load or the dynamic traffic load is exceeded, all of the pad and / or traffic loads must be supported by the soil around the wetwell and not by the wetwell itself.

#### NON-TRAFFIC LOAD (Figure H-I)





# J. WET HOLE INSTALLATION

# **A**CAUTION

Never allow an empty tank to remain in a wet hole, or a dry hole that may become wet unless anchoring and backfilling have been completed. Failure to anchor and backfill may damage the tank or surrounding property.

Firstly make site preparation as per section B.

Pump the water from the hole to maintain minimum water level. Add a minimum of 300mm of well-placed backfill material (Must Be Crushed Gravel) to the hole, and level the bed to assure uniform bottom support for the tank. Position the tank in the hole.

Partially ballast tank using water until it settles firmly on the prepared bed. Ballast level in a tank must never exceed water level in hole during installation. Use only enough ballast to sink the tank.

One tank is level and ballasted, carefully place concrete ballast as per section C. then processed to sections D,E (if applicable), F, G and H.

# TABLE 1

#### **External Anti Floatation Ribs:**

The wetwell bottom is designed to BS4994 to any resist buckling of the wetwell bottom from external water pressure and internal pressure, in the installed condition with a compacted base to (Figure I, below) and the perimeter of the wetwell including the anti-floatation Ribs embedded in concrete.

This table must be followed for the concrete slab design for all wetwells with fiberglass external ribs.

- These slabs are designed to AS3600.
- In some cases the slab and/or reinforcing design is controlled by temperature requirements and in other cases by flexure.
- Use minimum 20Mpa concrete
- Since some of the slab designs are controlled by temperature, the slab thickness should not be increased without the approval of a Design Engineer

	COLUMN 1.	COLUMN 2.	COLUMN 3.	COLUMN 4.	COLUMN 5.
Wetwell Dia. mm	Reinforcement REO 🛛 BAR (In Center of Slab, Ref-Figure 1.)	Required Slab Extension Around Wetwell (mm)	Slab Thickness (mm)	Required Ballast Extension Around Wetwell (mm)	Ballast Height (mm)
1200	1 @ 1800mm Dia. N12	400	200	300	400
1520	1 @ 1920mm Dia. N12	500	200	350	500
1850	1 @ 2250mm Dia. N12 & 1 @ 2650mm Dia. N12	550	200	400	600
2200	1 @ 2600mm Dia. N12 & 1 @ 3000mm Dia. FN12	700	200	500	700
2470	1 @ 2900mm Dia. N16 & 1 @ 3300mm Dia. N16	800	250	500	800
3000	1 @ 3400mm Dia. N16 & 1 @ 3800mm Dia. N16	900	300	700	1000
3500	1 @ 3900mm Dia. N20 & 1 @ 4800mm Dia. N20	1000	300	700	1200
4000	1 @ 4400mm Dia. N20 & 1 @ 4900mm Dia. N20	1100	350	750	1400







100 Montgomerie Road, Airport Oaks, Auckland New Zealand Phone: 09 930 7417 Email: sales@spel.co.nz

# spel.co.nz

SPEL Stormwater accepts no responsibility for any loss or damage resulting from any person acting on this information. The details and dimensions contained in this document may change, please check with SPEL Stormwater for confirmation of current specifications.